



COUNTY OF GLENN

Department of General Services- Facilities
453 E. County Road 49 ½
Willows, CA 95988
Phone: 530-934-6545
Facilities2@countyofglenn.net
www.countyofglenn.net

SCOTT H. DEMOSS
County Administrative Officer
525 W. Sycamore St. Suite B1
Willows, CA 95988
Phone: 530-934-6400
Fax: 530-934-6419
gcboard@countyofglenn.net

REQUEST FOR INFORMATION (RFI)

Solicitation Description: Willows Memorial Park Accessibility and Beautification Project

Solicitation Opening Date, Time: Friday, August 18, 2023 at 11:00 a.m.

Location: Glenn County Clerk of the Board
525 W. Sycamore St.
Willows, CA 95988

RFI Number: 002

RFI Date: Tuesday, August 15, 2023

Contact: Joe Bettencourt, Supervising Staff Services Analyst- General Services
Ricardo Valdez, Facilities Operation Manager- General Services
Facilities2@countyofglenn.net, (530) 934-6545

Return one properly executed copy of this RFI with bid response or prior to the Bid Opening Date/Time listed above.

- 1. Question:** Specification section 87-103E on page ES-3 states that all "Excavations for foundation shall be hand dug until clear of obstructions." Is it the County's intent for all light pole base foundations to be hand dug rather than augured?
1. Response: Excavation for foundation can be accomplished by use of machinery (backhoe, auger, hydro excavator etc.) or hand dug. Section 87-103E in the specifications has been modified to reflect this in Addendum #1, which is attached hereto for reference.
- 2. Question:** Specification section 87-2.03A on page ES-4, references the work for the service meter conduit system and states "all conduit shall be bored". Please confirm whether this applies to just the work associated with the new PG&E pole, meter and service, or if it applies to all conduit installation behind the meter for the project?
2. Response: All conduits that run across existing concrete sidewalk shall be bored. Contractor will have an option of trenching for all other conduits, if conduits run within planting/turf area. The high voltage wire from the existing transformer across the street (Murdock Ave) to new power pole will be hung overhead per PG&E requirement. Conduit from pole service drop to light/irrigation controller (service meter) pedestal shall be trenched per PG&E requirement.
- 3. Question:** Construction Note 6 on sheet DC-1 calls for "tubular steel fence" and specification section 206-7.1 calls for steel fencing materials to be tubular sections of hot rolled mild steel with a minimum of 11-gauge wall thickness, however Note D from detail 2 on sheet CD-2 calls for the steel fencing to be SCH 40 galvanized steel pipe. Please clarify.?
3. Response: Tubular fencing shall be pre-galvanized steel with a minimum of 11-gauge wall thickness. Addendum #1 addresses the above and is attached hereto for reference.

This RFI has been emailed to interested vendors as well as posted here: <http://www.countyofglenn.net/govt/bids>

Failure to acknowledge receipt of this RFI may result in rejection of the response.



COUNTY OF GLENN

Department of General Services- Facilities
453 E. County Road 49 ½
Willows, CA 95988
Phone: 530-934-6545
Facilities2@countyofglenn.net
www.countyofglenn.net

SCOTT H. DEMOSS
County Administrative Officer
525 W. Sycamore St. Suite B1
Willows, CA 95988
Phone: 530-934-6400
Fax: 530-934-6419
gcboard@countyofglenn.net

Addendum #1

Solicitation Description: Willows Memorial Park Accessibility and Beautification Project
Solicitation Opening Date, Time: Friday, August 18, 2023 at 11:00 a.m.

Location: Glenn County Clerk of the Board
525 W. Sycamore St.
Willows, CA 95988

Addendum Number: 001
Addendum Date: Tuesday, August 15, 2023
Contract: Joe Bettencourt, Supervising Staff Services Analyst- General Services
Ricardo Valdez, Facilities Operation Manager- General Services
Facilities2@countyofglenn.net, (530) 934-6545

Return one properly executed copy of this addendum with bid response or prior to the Bid Opening Date/Time listed above.

Modification 1: Specification section 87-1.03E on page ES-3 is deleted in its entirety and replaced with the below language.

87-1.03E Excavation and Backfilling for Electrical Systems. Excavation for foundation can be accomplished by use of machinery (backhoe, auger, hydro excavator etc.) or hand dug, until clear of obstructions. Contractor shall verify through Dig Alert (811) and visual inspection that there is no existing underground utility structure.

Modification 2: DWG. No. CD-2 (Sheet 23 of 26), Detail 2, General Notes, D. of the Plans is modified as follows:

All tubular steel fencing, railing and components shall be ~~SCH 40 galvanized steel pipe~~ galvanized steel pipe with a minimum of 11 gauge wall thickness.

This addendum has been emailed to interested vendors as well as posted here:

<http://www.countyofglenn.net/govt/bids>

Failure to acknowledge receipt of this addendum may result in rejection of the response.